



## MAPS 3 Transit/Modern Streetcar Mainline Preliminary Design

May 2015

# Report Significance (From April Meeting)



- Set design criteria
- Lock horizontal alignment
  - Start ROW process
  - Start geotech borings
  - Start rail procurement
  - Start utility potholing
  - Confirm rail location in traffic lanes
- Check cost budgets
- Launch final design

# Report Contents (From April Meeting)




- Design criteria
- Stop concept
- Bridge structural evaluation
- Traction power substations (TPSS)
- Overhead contact system (OCS)
- Utilities (public and private) inventory
- Traffic analysis
- ADA inventory
- Rights of way (TPSS and corners)
- Cost estimate

# Key Issues for Approval

- Lock route alignment
- Confirm stop map
- Consider turnback options
  - 4<sup>th</sup> Street
  - 6<sup>th</sup> Street
- Update Min/Max Off Wire
- Confirm traffic mgmt.
- Review costs

# Route and Stop Locations



Terminal (Dwell) Point


Terminal (Dwell) Point

# Turnback Options



6<sup>th</sup> Street  
Turnback  
Option

# 4<sup>th</sup> Street Turnback



# Turnback Options – Path Forward




- Evaluate 6<sup>th</sup> Street vs. 4<sup>th</sup> Street Option
- Include in design as additive alternate if budget permits



# Minimum Off Wire

- 3 to 4 and 20 to 21 are minimum required



PRELIMINARY


# Maximizing Vehicle Capability

- Stop to Stop
- Travel Time
- No extra time charging time from mainline (dwells)
- Ease of operations and maintenance
  - Minimize pantograph movements
  - Minimize OCS maintenance
- Vehicle capability (under confirmation by Inekon)
  - Battery performance
  - Operate 18 hrs with battery charge range
- Safety – Pantograph movements and operations requirements

Recommendation: Extend the minimum wireless to realize cost savings potential

# Maximum Off Wire

- 4 to 8 is likely within battery capability
- 8 to 9 too steep to stay off-wire
- 17 to 20 is likely within battery capability
- No additional pantograph movements
- Stop 1 (Bricktown terminus) remains wired
- Stop 14 (Midtown terminus) remains wired



PRELIMINARY:  
SUBJECT TO  
INEKON  
CONFIRMATION

ON WIRE (61%)  
OFF WIRE (39%)  
(not including  
Hudson to Maint. or  
EK Gaylord)

# OCS – Typical Mid Block



# Traffic Updates



- 10<sup>th</sup> Street – Two lanes each way
  - Eastbound streetcar in south lane
  - Westbound traffic has parallel parking option
  - Helps peak traffic in both directions
- Broadway – Two lanes each way
  - Helps Southbound peak hour traffic
  - Helps Northbound streetcar movement
  - Reconfiguration of Eastside parking

# Budget Status -- Project



Item	Currently Approved Budget	Current Status (30% Submittals)	Breakdown of Current Status (30%)	Variance
Transit Investigation and Standards	\$2,136	\$2,067		(\$69)
Transit Phase 1 A&E/Design/Testing/Admin	\$15,401	\$15,401		\$0
Transit Phase 1 Land Acquisition & Site Prep	\$2,500	\$2,500		\$0
Land Acquisition			\$500	
Site Prep (Private Utility Adjustments)			\$2,000	
Transit Rail Procurement	\$4,650	\$3,522		(\$1,128)
Transit Car Procurement	\$26,000	\$22,958		(\$3,042)
Transit Phase 1 Route Construction and FF&E	\$50,825	\$52,755		\$1,930
Mainline			\$49,096	
Hudson and S&MF Yard			\$3,659	
Maintenance Construction and FF&E	\$4,500	\$4,500		\$0
HUB Construction	\$9,810	\$9,810		\$0
Hudson Road Design/Construction		\$791		\$791
Transit Phase 1 Project Contingency	\$4,337	\$4,337		\$0
Transit Phase 2 A&E Design/Testing/Admin	\$1,160	\$1,160		\$0
Transit Phase 2 Construction	\$7,137	\$7,137		\$0
Transit Phase 2 Project Contingency	\$359	\$359		\$0
<b>TOTAL MAPS 3 PROJECT</b>	<b>\$128,815</b>	<b>\$127,297</b>		<b>(\$1,518)</b>
NOTE: Bolded items above are reflected in Mainline Construction Cost Estimate Table				

← Current Status: Under Budget

# Budget Status -- Mainline



## Potential Deducts:

- Hudson OCS spacing (124' vs. 62')
- OCS reduction for max. off-wire
- TPSS reduction
- Private utilities relocation
- Bricktown terminal pocket track

## Potential Additions:

- Turnbacks
- Combined poles/streetlighting
- Public utilities relocations

Costs to be diligently evaluated as design progresses toward 60%

# Next Steps



- Inekon off-wire configuration confirmation (ongoing)
- Combined pole decisions
- Traffic pre-emption priorities
- Potholing
- Geotech
- Utilities coordination and decisions (public, private)
- Rail procurement
- Commence work on Special Questionnaire for Bidders
- 60% design drawings



- Vehicle
  - Inekon contract being negotiated
  - Charge/discharge of batteries being confirmed
- Storage and Maintenance Facility (S&MF)
  - Value Engineering occurring
  - Preliminary report and drawings in June 2015
- Operations
  - Fare method determination
  - Operations plan
  - Safety and Security Mgmt. Plan drafted



## MAPS 3 Transit/Modern Streetcar Mainline Preliminary Design

May 2015