

APRON AND HEADWALL BAR LIST

MARK	SIZE	FORM	6' SPAN			7' SPAN			8' SPAN			9' SPAN			10' SPAN			11' SPAN			12' SPAN		
			NO.	LENGTH	LENGTH VARIATION	NO.	LENGTH	LENGTH VARIATION	NO.	LENGTH	LENGTH VARIATION	NO.	LENGTH	LENGTH VARIATION	NO.	LENGTH	LENGTH VARIATION	NO.	LENGTH	LENGTH VARIATION	NO.	LENGTH	LENGTH VARIATION
ABD1	#4	STR.	48	4'-3"		54	4'-3"		60	4'-3"		66	4'-3"		72	4'-3"		78	4'-3"		84	4'-3"	
ABD2	#4	BNT.	4	5'-0"		4	5'-0"		4	5'-0"		4	5'-0"		4	5'-0"		4	5'-0"		4	5'-0"	
AD	#4	STR.	4	23'-7"		4	23'-7"		4	23'-7"		4	23'-7"		4	23'-7"		4	23'-7"		4	23'-7"	
AL1	#4	STR.	48	21'-7"		54	21'-7"		60	21'-7"		66	21'-7"		72	21'-7"		78	21'-7"		84	21'-7"	
AL2	#4	STR.	44	10'-10" AVG.	2'-3" TO 19'-5"	44	10'-10" AVG.	2'-3" TO 19'-5"	44	10'-10" AVG.	2'-3" TO 19'-5"	44	10'-10" AVG.	2'-3" TO 19'-5"	44	10'-10" AVG.	2'-3" TO 19'-5"	44	10'-10" AVG.	2'-3" TO 19'-5"	44	10'-10" AVG.	2'-3" TO 19'-5"
AT1	#4	STR.	4	44'-10"		4	47'-10"		4	50'-10"		4	53'-10"		4	56'-10"		4	62'-8"		4	65'-8"	
AT2	#4	STR.																		3	63'-11" AVG.	62'-9" TO 65'-1"	
AT3	#5	STR.																		3	63'-11" AVG.	62'-9" TO 65'-1"	
AT4	#4	STR.	21	32'-8" AVG.	21'-1" TO 44'-3"	21	35'-8" AVG.	24'-1" TO 47'-3"	21	38'-8" AVG.	27'-1" TO 50'-3"	21	41'-8" AVG.	30'-1" TO 53'-3"	21	44'-8" AVG.	33'-1" TO 56'-3"	21	48'-0" AVG.	36'-5" TO 59'-7"	18	49'-3" AVG.	39'-5" TO 59'-1"
AT5	#5	STR.	21	32'-8" AVG.	21'-1" TO 44'-3"	21	35'-8" AVG.	24'-1" TO 47'-3"	21	38'-8" AVG.	27'-1" TO 50'-3"	21	41'-8" AVG.	30'-1" TO 53'-3"	21	44'-8" AVG.	33'-1" TO 56'-3"	21	48'-0" AVG.	36'-5" TO 59'-7"	18	49'-3" AVG.	39'-5" TO 59'-1"
CH	#4	STR.	4	21'-0"		4	24'-0"		4	27'-0"		4	30'-0"		4	33'-0"		4	36'-4"		4	39'-4"	
CL1	#4	BNT.	26	4'-4"		29	4'-4"		32	4'-4"		35	4'-4"		38	4'-4"		41	4'-4"		44	4'-4"	
CL2	#4	BNT.	26	4'-4"		29	4'-4"		32	4'-4"		35	4'-4"		38	4'-4"		41	4'-4"		44	4'-4"	

- ① 4 SETS OF 11 BARS
- ② ALL BARS OVER 60" LONG INCLUDES 2'-6" LAP

NOTE:
QUANTITIES ARE FOR ONE END SECTION WHICH INCLUDES ONE HEADWALL, ONE APRON AND TWO WINGWALLS. PIPE RAILING IS BASED ON PLAN DIMENSION AT CENTERLINE OF RAILING.

QUANTITIES




ITEM	UNIT	6' SPAN	7' SPAN	8' SPAN	9' SPAN	10' SPAN	11' SPAN	12' SPAN
CLASS AA CONCRETE	C.Y.	33.8	36.2	38.6	40.9	43.3	45.9	48.3
REINFORCING STEEL	LB.	4,630	4,850	5,050	5,290	5,530	5,770	6,000
PIPE RAILING	L.F.	69	72	75	78	81	84	87

APRON VARIABLES

SPAN	DIMENSIONS			NUMBER OF BARS		
	R	Q	K	N	S	V
6'	21'-4"	22'-7"	26	24		21
7'	24'-4"	24'-1"	29	27		21
8'	27'-4"	25'-7"	32	30		21
9'	30'-4"	27'-1"	35	33		21
10'	33'-4"	28'-7"	38	36		21
11'	36'-8"	30'-3"	41	39		21
12'	39'-8"	31'-9"	44	42	3	18

WINGWALL DIMENSIONS


SPAN	W	D	F
6'	10"	4 11/16"	11 15/16"
7'	10"	4 11/16"	11 15/16"
8'	10"	4 11/16"	11 15/16"
9'	10"	4 11/16"	11 15/16"
10'	10"	4 11/16"	11 15/16"
11'	11"	2 15/16"	1'-1 15/16"
12'	11"	2 15/16"	1'-1 15/16"



APPROVED BY: DATE: 6/22/2023
ERIC J. WENGER, P.E.
CITY ENGINEER
THESE STANDARD DRAWINGS AND ASSOCIATED CALCULATIONS HAVE BEEN PREPARED BY CEC CORPORATION UNDER CONTRACT WITH THE CITY OF OKLAHOMA CITY


R.C.B. CULVERTS - END SECTION DETAILS
TRIPLE CELL - 6' HEIGHT - 0° SKEW
SHEET NO. 1 OF 2

REVISION NO.
DATE




WINGWALL ELEVATION

SEE STD. RCB-015 PipeRailing FOR DETAILS OF RAIL REQUIRED ON TOP OF HEADWALL AND WINGS



TYPICAL SECTION THRU WING



ADJUSTMENT IN NUMBER OF BARREL BARS IN END SECTION


SPAN	BAR MARKS								
	A1	A2	A3	B1	B2	C1	C2	C3	C4
6'	+1			+2	+2	-4	-4	+2	+2
7'	+1					-4	-4	+2	+2
8'		-1				-4	-4	+2	+2
9'		-1				-4	-4	+2	+2
10'		-1				-4	-4	+2	+2
11'		-1				-4	-4	+2	+2
12'		-1	-2			-4	-4	+2	+2

NOTE:
TO CONSTRUCT ONE END SECTION AS SHOWN, THE NUMBER OF BARS SHOWN NEED TO BE ADDED TO OR SUBTRACTED FROM THE TOTAL WEIGHT OF REINFORCING FOR THE BARREL. THIS WEIGHT ADJUSTMENT IS INCLUDED IN THE END SECTION QUANTITY. SEE BARREL DETAILS FOR BAR LENGTHS, SIZES AND BENDS.


WINGWALL BAR LIST
ONE WINGWALL SHOWN, TWO REQUIRED

MARK	SIZE	NO.	FORM	LENGTH	LENGTH VARIATION
WD	#7	14	BNT.	6'-6"	
WH1	#4	4	STR.	23'-7"	
WH2	#4	12	STR.	12'-3" AVG.	3'-8" TO 20'-10"
WH3	#5	2	STR.	23'-8"	
WL1	#5	21	BNT.	9'-2"	
WL2	#5	9	BNT.	6'-9"	
WL3	#5	4	BNT.	6'-9" AVG.	6'-4" TO 7'-2"
WT1	#4	21	STR.	2'-4"	
WT2	#4	2	STR.	8'-0"	
WT3	#4	19	STR.	5'-3" AVG.	2'-8" TO 7'-10"
WT4	#4	4	STR.	2'-7" AVG.	2'-2" TO 3'-0"
WV1	#5	2	STR.	8'-0"	
WV2	#5	19	STR.	5'-3" AVG.	2'-8" TO 7'-10"
U	#4	1	BNT.	4'-6"	

① 2 SETS OF 6 BARS



HEADWALL DETAIL AT EXTERIOR WALL



HEADWALL DETAIL AT INTERIOR WALL

REVISION NO.

DATE

APPROVED BY: ERIC J. WENGER, P.E. CITY ENGINEER
DATE: 6/22/2023
THESE STANDARD DRAWINGS AND ASSOCIATED CALCULATIONS HAVE BEEN PREPARED BY CEC CORPORATION UNDER CONTRACT WITH THE CITY OF OKLAHOMA CITY.